

Project: 216041-48735
Client: SABIC
Doc. No: 05-216041-48735/C.03e/0001/B

Issue: B
Issue Date: 6/10/2023

		Unit	Quantity
1	<u>General</u>		
2	<u>Civil works</u>		
2.1	<u>Concrete works in situ</u>		
2.1.1	Excavation works	m ³	232,5
2.1.2	Sewer line HDPE	m	17,0
2.1.3	Lean concrete C20/25	m ²	143,4
2.1.4	Concrete C35/45	m ³	64,9
2.1.5	Smooth formwork	m ²	60,1
2.1.6	Stelcon Plates	m ²	132,0
2.1.7	Stabilized sand foundation	m ³	52,8
2.1.8	Reinforcement (100 kg/m ³)	kg	6488,9
2.1.9	No of Piles	pcs	21,0
2.1.10	Backfill	m ³	97,6
2.1.11	Anchors	m ³	64,0
2.1.12	Grouting	l	43,2
2.1.13	Crash protection (poles) at columns	pcs	5,0
2.1.14	Crash barrier at blower	m	4,0
2.2	<u>Structural works</u>		
2.2.1	Structural steel brackets to support pipes, Anchor bay steel & shelter for pipe in one of the grid width	kg	1375,2
2.2.2	Structural steel platform at exhaust	kg	518,1
2.2.3	Grating	m ²	9,0
2.2.4	Guard railing	m	14,0
2.2.5	Stair treads	pcs	8,0
2.2.6	Anchors	pcs	10,0
2.3	<u>Cutout & closeout work</u>		
2.3.1	Cutout/opening in existing structure	pcs	33,0
2.3.2	Closeout of opening in existing structure	pcs	33,0
2.4	<u>Repositioning of caged ladder</u>		
2.4.1	Repositioning of caged ladder at vessel (clash 8)	pcs	1,0