

WATERBALANS

Project: Bredius
 Projectnummer: 18-167-001
 Datum: 25-apr-18



OmniformGroup

Bestaand water		
Nr.	Oppervlakte	Eenh.
B1	5	m2
B2	26	m2
B3	561	m2
B4	27	m2
B5	10	m2
B6	15	m2
B7	13	m2
B8	109	m2
B9	38	m2
B10	78	m2
B11	219	m2
B12	38	m2
B13	127	m2
	1.266	m2

Vervallen water		
Nr.	Oppervlakte	Eenh.
V1	-623	m2
V2	-57	m2
V3	-27	m2
V4	-83	m2
V5	-119	m2
V6	-93	m2
V7	-379	m2
V8	-691	m2
V9	-9	m2
V10	-15	m2
V11	-629	m2
V12	-14	m2
V13	-312	m2
V14	-72	m2
V15	-25	m2
V16	-536	m2
V17	-8	m2
	-3.692	m2

Vervallen verharding		
Nr.	Oppervlakte	Eenh.
VVH1	-2.685	m2
VVH2	-49	m2
	-2.734	m2

Nieuw water		
Nr.	Oppervlakte	Eenh.
N1	615	m2
N2	868	m2
N3	278	m2
N4	219	m2
N5	403	m2
N6	179	m2
N7	621	m2
N8	809	m2
N9	39	m2
N10	310	m2
N11	924	m2
N12	1.085	m2
N13	10	m2
N14	9	m2
	6.369	m2

Nieuwe verharding		
Nr.	Oppervlakte	Eenh.
VH1	2.043	m2
VH2	388	m2
VH3	3.677	m2
VH4	4.985	m2
VH5	1.142	m2
VH6	503	m2
VH7	520	m2
VH8	536	m2
VH9	908	m2
VH10	650	m2
	15.352	m2

Sportvelden		
Nr.	Oppervlakte	Eenh.
NG1	7.793	m2
KG1	7.793	m2
KG2	3.648	m2
KG3	5.922	m2
KG4	5.896	m2
	31.052	m2

Bebouwing		
Nr.	Oppervlakte	Eenh.
BB1	1.081	m2
BB2	490	m2
BB3	1.351	m2
BB4	490	m2
BB5	1.620	m2
BB6	490	m2
BB7	1.220	m2
BB8	125	m2
BB9	1.750	m2
	8.617	m2

Totalen		
Omschrijving	Oppervlakte	Eenh.
Bestaand water	1.266	m2
Vervallen water	-3.692	m2
Nieuw water	6.369	m2
	3.943	m2
Vervallen verharding	-2.734	m2
Nieuwe verharding	15.352	m2
Sportvelden (50%)	15.526	m2
Bebouwing	8.617	m2
	36.761	m2
Te compenseren 10%	3.676	m2
Waterbalans	267	m2