

Waterbalans N282- N260A, overzicht

Werkvakken zijn de bladnummers op de tekeningen zoals bijgevoegd bij de aanvraag watervergunning

Onderdeel	Werkvak 1	Werkvak 2A	Werkvak 2B	Werkvak 3	Werkvak 4	Werkvak 5	Werkvak 6	Werkvak 7	Werkvak 8A	Werkvak 8B	Werkvak 9	Totaal	
<i>verharding</i>													
Verharding bestaand	12134.89	5595.63	5691.56	7064.39	7806.48	6577.85	5428.15	20255.44	4719.59	7039.11	4107.98	86421.06	m ²
Verharding nieuw	14048.46	8775.74	8813.94	8654.45	11297.28	7120.28	8802.01	13319.08	8656.72	12924.42	6350.84	108763.23	m ²
verharding toename	1913.57	3180.11	3122.37	1590.05	3490.81	542.43	3373.86	-6936.35	3937.14	5885.32	2242.86	22342.16	m ²
bergingseis (60mm)	114.81	190.81	187.34	95.40	209.45	32.55	202.43	-416.18	236.23	353.12	134.57	1340.53	m ³
<i>oppervlaktewater</i>													
Sloot bestaand	517.28	0.00	0.00	0.00	718.98	1189.67	1508.61	1549.65	1259.69	517.80	304.95	7566.63	m ²
Sloot nieuw	860.34	1375.21	1381.31	210.30	0.00	641.84	2810.20	2620.53	2245.27	997.16	757.43	13899.59	m ²
sloot toename	343.06	1375.21	1381.31	210.30	-718.98	-547.83	1301.59	1070.88	985.58	479.36	452.48	6332.97	m ²
berging (obv waterschijf)	102.92	412.56	414.39	63.09	-215.69	-164.35	390.48	321.26	295.67	143.81	135.75	1899.89	m ³
<i>rwa-systeem</i>													
riool	0.00	0.00	0.00	0.00	116.00	0.00	0.00	0.00	0.00	0.00	0.00	116.00	m ³
kratten	0.00	0.00	0.00	0.00	803.00	0.00	0.00	0.00	0.00	0.00	0.00	803.00	m ³
grindkoffers	7.62	0.00	0.00	0.00	0.00	0.00	0.00	14.06	34.86	117.43	0.00	173.96	m ³
berging rwa-systeem	7.62	0.00	0.00	0.00	919.00	0.00	0.00	14.06	34.86	117.43	0.00	1092.96	m ³
toename water	110.53	412.56	414.39	63.09	703.31	-164.35	390.48	335.33	330.53	261.23	135.75	2992.85	m ³
overschot tov eis	-4.28	221.76	227.05	-32.31	493.86	-196.89	188.05	751.51	94.31	-91.89	1.17	1652.32	m ³

waterschijf 0.3 m

hoogte grindkoffers varieert tussen 0,8 en 1,0m

o.b.v. G020828-TEK-2740
d.d. 12-06-2023